

NICAL / COMMON NAME	CONTAINER	<u>SIZE</u>	<u>SPACING</u>	<u>QTY</u>
grandidentatum `Schmidt` / Rocky Mountain Glow Maple	B & B	1.5" cal	as shown	3

- Top of root ball shall be flush with finished grade.

-Prior to mulching, lightly tamp soil around the root ball in 6" lifts to brace tree. Do not over compact. When the planting hole has been backfilled, pour water around the root ball to settle the soil.

-4" layer of mulch. No more than 1" of mulch on top of root ball. (See specifications for mulch).

Notes: 1— Trees shall be of quality prescribed in crown observations and root observations details and specifications.

2- See specifications for further requirements related to this detail.

> URBAN TREE FOUNDATION © 2014 OPEN SOURCE FREE TO USE

FX-PL-FX-TREE-05

