



PUBLIC WORKS DEPARTMENT

To: La Center 2025 Guardrail Repair Project Bidders

Date: February 11, 2025

Item: Addendum # 2

Guardrail note revisions:

The following is an addendum to clarify about erosion control requirements.

Section 1-09 Measurement and Payment

Section 5-01 of the City of La Center Erosion Control Manual

The sections will be modified as follows:

Section 5-01 of the City of La Center Standards for Erosion Control Section 5 of the Engineering Standards for Construction shall be used. A Stormwater Pollution Prevention Plan (SWPPP) and a Certified Erosion and Sediment Control Lead (CESCL) will not be required for this project.

Payment

Payment for Mobilization according to WSDOT standards and Erosion Control Measures per the City of La Center standards shall be paid as lump sum bid items and shall include all labor and materials to complete the items.

Section 8-11 Guardrail

8-11.3(1)D Removing Guardrail and Guardrail Anchor

The guardrail replacement shall be modified as follows:

Removal of guardrail shall include removal of the rail elements, timber blocks, steel and timber posts transition sections, terminal sections and hardware. The existing steel posts, timber blocks and hardware, which are not damaged, may be salvaged and reused for new guardrail installation. **As an option, steel posts can be used to replace the existing damaged timber posts that need to be replaced, as identified on the plans, provided there is no cost difference to the City of La Center.**

Sincerely,

Anthony Cooper, PE
City of La Center
City Engineer/Assistant Public Works Director