

TEST	SPECIFICATIONS	FREQUENCY	TESTING AGENCY	COMMENTS
SUBGRADE CUT COMPACTION	WSDOT 2-06.3	ONCE EVERY 500 FEET	CERTIFIED LAB	(95%) PRIOR TO BASE ROCK
SUBGRADE FILL COMPACTION	WSDOT 2-06.3	ONCE EVERY 500 FEET	CERTIFIED LAB	(95%) PRIOR TO BASE ROCK
UTILITY BACKFILL COMPACT.	WSDOT 2-06.3	EVERY 500 FEET OF TRENCH	CERTIFIED LAB	PRIOR TO BASE ROCK 95%
EASEMENT UTIL. BACKFILL	WSDOT 2-06.3	EVERY 500 FEET OF TRENCH	CERTIFIED LAB	PRIOR TO FINAL ACCEPTANCE 95%
LOT AREA COMPACTION	AASHTO T-99	MIN 1/ LOT FILL OVER 1'	CERTIFIED LAB	PRIOR TO FINAL ACCEPTANCE
BACTERIA WATER SAMPLE	WSDOH	AS REQ'D. BY CPU	CERTIFIED LAB	PRIOR TO PRESSURE TEST & BASE ROCK
WATER PRESSURE TEST	WSDOT 7-09.3	MAIN, SERVICE, F.H., BY CPU	CONTRACTOR	PRIOR TO BASE ROCK
PRESS. SEWER PRESSURE TEST	WSDOT 7-17.3	MAIN, SERVICE, AIR/VAC	CONTRACTOR	PRIOR TO BASE ROCK
PRESS. SEWER DEFLECTION TEST	WSDOT 7-17.3	MAIN, SERVICE	CONTRACTOR	PRIOR TO BASE ROCK
GRAV. SEWER AIR TEST	WSDOT 7-17.3	MAIN AND LATERALS	LAB/CONTRACTOR	PRIOR TO BASE ROCK
GRAV. SEWER VAC. TEST MH	WSDOT 7-17.3	AFTER INSTALLATION	LAB/CONTRACTOR	AFTER PAVEMENT INSTALLED
GRAV. SEWER DEFLECTION TEST	WSDOT 7-17.3	AFTER INSTALLATION	CONTRACTOR	PRIOR TO BASE ROCK
GRAV. SEWER TV TEST	WSDOT 7-17.3	AFTER INSTALLATION	CONTRACTOR	PRIOR TO PAVING
PRESSURE WASH SAN. SEWER	-	AS DIRECTED PER CITY	CONTRACTOR	AS DIRECTED PER CITY
BASE ROCK GRADING	WSDOT 9-03.9	ONE PER SOURCE	CERTIFIED LAB	PRIOR TO PLACEMENT
BASE ROCK COMPACTION	WSDOT 4-04.3	1/ EVERY 1,000 LINEAL FEET	CERTIFIED LAB	PRIOR TO TOP ROCK (95% DENSITY)
TOP ROCK GRADING	WSDOT 9-03.9	ONE PER SOURCE	CERTIFIED LAB	PRIOR TO PLACEMENT
TOP ROCK COMPACTION	WSDOT 4-04.3	1/ EVERY 1,000 LINEAL FEET	CERTIFIED LAB	PRIOR TO PAVEMENT (95% DENSITY)
HMA GRADE & OIL CONTENT	WSDOT 9-03.8	ONE PER SOURCE	CERTIFIED LAB	PRIOR TO PLACEMENT
HMA COMPACTION	WSDOT 2-06.3	5 TESTS PER DENSITY LOT	CERTIFIED LAB	91% OF MAXIMUM RICE DENSITY
SUBGRADE GRADE CK ELEV	WSDOT	PER STATION (0+25)	CONTRACTOR	PRIOR TO ROCK
BASE ROCK GRADE CK ELEV	WSDOT	PER STATION (0+50)	CONTRACTOR	PRIOR TO TOP ROCK
TOP ROCK GRADE CK ELEV	WSDOT	PER STATION (0+50)	CONTRACTOR	PRIOR TO PAVEMENT
CONCRETE TESTING	WSDOT 5-05.3	PER STANDARD SPECS	CERTIFIED LAB	
STORM SEWER EXFILTRATION TEST	WSDOT 7-04.3	MAIN, MH	CONTRACTOR	PRIOR TO BASE ROCK
STORM SEWER INFILTRATION TEST	WSDOT 7-04.3	MAIN, MH	CONTRACTOR	PRIOR TO BASE ROCK
STORM SEWER AIR TEST	WSDOT 7-04.3	MAIN	CONTRACTOR	PRIOR TO BASE ROCK

# UTILITY AND ROAD TESTING REQUIREMENTS

PLAN #

CITY OF LA CENTER APPROVED

REVISIONS:	DATE:	DRAWN:	DESIGNED:



*Bart Stapp, PE 7/23/09*

C-1

CITY ENGINEER

DATE