


1. ALL MATERIALS, WORKMANSHIP AND INSTALLATION OF STORM SEWERS SHALL BE IN CONFORMANCE WITH THE LATEST EDITION OF THE "CITY OF LA CENTER ENGINEERING STANDARDS FOR PUBLIC WORKS CONSTRUCTION" AND THE LATEST EDITION OF THE "WSDOT STANDARD SPECIFICATIONS FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION", HEREINAFTER REFERRED TO AS THE "STANDARD SPECIFICATIONS", PREPARED BY THE WASHINGTON STATE CHAPTER OF THE AMERICAN PUBLIC WORKS ASSOCIATION (APWA) AND THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION, EXCEPT AS NOTED HEREIN OR ON THE STANDARD PLANS.
2. THE CONTRACTOR IS TO VERIFY ALL INVERT AND TOP ELEVATIONS OF EXISTING STORM SEWERS, CENTERLINE AND TOP OF CURB ELEVATIONS, AND REPORT ANY DISCREPANCIES IMMEDIATELY TO THE ENGINEER.
3. ALL STORM SEWER CONSTRUCTION IS SUBJECT TO INSPECTION, AND APPROVAL, PRIOR TO COVER BY THE CITY OF LA CENTER. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF CONSTRUCTION. A PRE-CONSTRUCTION MEETING IS REQUIRED PRIOR BEGINNING OF THE CONSTRUCTION.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO THE START OF CONSTRUCTION AND TO NOTIFY THE ENGINEER OF ANY POTENTIAL CONFLICTS. THE CONTRACTOR SHALL DIG TEST HOLES OVER ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION TO DETERMINE THEIR EXACT LOCATION. CALL 1-800-424-5555, (NORTHWEST UTILITY NOTIFICATION CENTER), FOR MARK-UP OF EXISTING UTILITIES, A MINIMUM OF 2 WORKING DAYS PRIOR TO START OF CONSTRUCTION.
5. IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER AND/OR CONTRACTOR TO PROCURE ALL APPLICABLE PERMITS, LICENSES AND CERTIFICATES RELATIVE TO THE TRADES TO COMPLETE THE PROJECT AND FOR THE USE OF SUCH WORK WHEN COMPLETED. COMPLIANCE SHALL BE AT ALL LEVELS, FEDERAL, STATE AND CITY, RELATING TO THE PERFORMANCE OF THIS WORK.
6. THE CONTRACTOR SHALL OBTAIN ALL OFFSITE CONSTRUCTION EASEMENTS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THAT ALL OFFSITE UTILITIES EASEMENTS HAVE BEEN OBTAINED BY THE OWNER PRIOR TO THE COMMENCEMENT OF ANY OFFSITE CONSTRUCTION.
7. THE CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL PLAN TO THE PUBLIC WORKS DEPARTMENT THAT MUST BE APPROVED BY THE PUBLIC WORKS DEPARTMENT PRIOR TO CONSTRUCTION.
8. ALL CATCH BASINS AND CURB INLETS SHALL BE STENCILED AS FOLLOWS: "DUMP NO WASTE-DRAINS TO STREAM".
9. SIGNS THAT READ: "WATER QUALITY FILTER-PLEASE LEAVE VEGETATED" SHALL BE INSTALLED EVERY 50 FEET ON FENCE OR POSTS ALONG WATER QUALITY BIOFILTRATION SYSTEMS.
10. VEGETATION IN BIOFILTRATION SYSTEMS SHALL BECOME FULLY ESTABLISHED PRIOR TO COMMENCING WITH INSTALLATION OF A.C. PAVEMENT FOR ALL AREAS DRAINING INTO THE WATER QUALITY SYSTEM. VEGETATION IN BIOFILTRATION SYSTEMS TO BE THE FOLLOWING GRASS SEED MIX (PROPORTIONS GIVEN BY WEIGHT):

40% REDTOP BENTGRASS, 30% RED FESCUE, 20% TALL FESCUE, 5% PERENNIAL RYE, 5% RUSSIAN WILD RYE.
11. PIPES OVER 12" DIA. SHALL HAVE A CHILD PROTECTION DEVICE AT INFLUENT END.
12. ALL STORM MANHOLES INSTALLED WITHIN AN EASEMENT OR OUTSIDE THE CITY RIGHT-OF-WAY SHALL HAVE LOCKING LID COVERS.
13. MATERIAL CERTIFICATION FOR ALL STORM MANHOLES, CATCHBASINS, AND CURB INLETS SHALL BE PROVIDED TO THE CITY INSPECTOR.
14. ALL ROOF AND LOWPOINT DRAINS TO BE DIRECTED TO APPROVED DRAINAGE PER PLANS.
15. ALL TRENCH BACKFILLING WILL CONFORM TO STANDARD DETAIL SS-4. PIPE BEDDING WILL CONFORM TO STANDARD DETAIL SS-5.
16. ALL STORM SEWER CLEANOUTS WILL MEET THE REQUIREMENTS OF STANDARD DETAIL SS-14.

GENERAL STORMWATER NOTES

PLAN #

	CITY OF LA CENTER APPROVED	REVISIONS:	DATE:	DRAWN:	DESIGNED:	SM-1
	<i>Bart Stepp, PE 7/23/09</i>					
	CITY ENGINEER					
	DATE					